APPENDIX B
BITUMINOUS SURFACE TREATMENT SEAL COAT 3/8"-#10 - 2012
CITY OF PROSSER STREETS

Asphalt application rate of 0.35 gal/sq yd

Street Name	From	To	Length (Mi)	Width (Ft)	(Sq Yd)	3/8" to #10 (C.Y.)	CRS-2P (Ton)	Pickup Sweep
CASI CT	CUL-DE-SAC	NUNN	0.10	38	2,229	22.29	3.25	X
CHARDONAY	MERLOT	WINE COUNTRY	0.23	38	5,127	51.27	7.48	X
GAP	WINE COUNTRY	OIEH	0.24	38	5,350	53.50	7.80	X
MERLOT	WAMBA	BEGIN CURB	0.13	28	2,135	21.35	3.11	X
MERLOT	BEGIN CURB	END CURB	0.40	38	8,917	89.17	13.00	X
NORTH RIVER RD	WINE COUNTRY	CITY/COUNTY	0.10	28	1,643	16.43	2.40	X
NUNN	WINE COUNTRY	END CURB	0.23	38	5,127	51.27	7.48	X
NUNN	END CURB	CITY/COUNTY	0.31	18	3,274	32.74	4.77	
OIEH	CITY/COUNTY	BEGIN CURB	0.42	22	5,421	54.21	7.91	
OIEH	BEGIN CURB	END CURB	0.07	30	1,232	12.32	1.80	X
OIEH	END CURB	BEGIN WIDENING	0.20	22	2,581	25.81	3.76	
OIEH	BEGIN WIDENING	WINE COUNTRY	0.05	36	1,056	10.56	1.54	
OIEH	WINE COUNTRY	END CURB	0.08	30	1,408	14.08	2.05	X
OIEH	END CURB	WAMBA	0.15	20	1,760	17.60	2.57	
OIEH	WAMBA	CITY/COUNTY	0.15	20	1,760	17.60	2.57	
WAMBA	WINE COUNTRY	END CURB	0.06	38	1,338	13.38	1.95	X
WAMBA	END CURB	OIEH	0.14	22	1,807	18.07	2.64	X
WAMBA	OIEH	END CURB	0.14	28	2,300	23.00	3.35	X
WAMBA	END CURB	BEGIN CURB	0.05	22	645	6.45	0.94	X
WAMBA	BEGIN CURB	END CURB	0.25	28	4,107	41.07	5.99	X
WAMBA	END CURB	MERLOT	0.06	24	845	8.45	1.23	X
WINE COUNTRY	STATE/CITY	NORTH END BRIDGE	0.88	38	19,618	196.18	28.61	X
TOTALS			4.44		79,681	796.81	116.20	